

Project (If Applicable)		TRA Ref. No.	DOUS-TRA-028	
Location / Worksite				
Sub Location / Area				
Equipment Spread (Optional)				
Task / Activity	OIL TRANSFER			
Approver				
Responsible Person				
Date TRA Created				
Reference Supporting Documents & Task Plan				
S3RA:	Hot Work Checklist:			
Task Plan:	Work at Height Checklist:			
Lift Plan:	Confined Space Work Checklist:			
PTW:	Electrical Equipment Checklist:			
COSHH / SDS:	Electrical Isolation Checklist:			
Rescue Plan:	Machinery Isolation Checklist:			
Work Equipment Assessment:	Pressure Systems Checklist:			
Other:	Other:			
Reason for TRA (Tick where Applicable)				
Identification of New Task	Annual Review	Review following Incident	Management of Change Record	Other, Please Specify
☐	☐	☐	☐	☐
Other (Details):				
TRA Participants				
Name	Position		Signature	
NOTE: STANDARD PPE OF SAFETY FOOTWEAR, SAFETY HELMET, COVERALLS, GLASSES AND GLOVES MUST BE WORN. ANY ADDITIONAL PPE REQUIRED SHALL BE CAPTURED IN THE MITIGATING CONTROLS SECTION OF THE TRA TEMPLATE BELOW.				

No.	Task /Activity	Hazard and Consequence		Initial Risk			Mitigating Controls	Residual Risk		
	Sequential Steps	Hazard	Consequence	Probability	Consequence Severity	Risk Rating	Measures to Reduce Risk to ALARP	Probability	Consequence Severity	Risk Rating
1	Review TRA and TBT	Miscommunication	Personnel Injury / Environmental Pollution	1	2	2	Situational awareness and proper use of PPE. Hard hats, impact gloves, cotton gloves, latex gloves, steel toed boots, safety glasses, side shields and face shield	1	1	1
2	Prior to any task being undertaken ensure that all personnel are aware of the hazards involved.	Electrical shock, possible slips trips and falls. Pinch points poor body position. Hydraulic discharge and spills.	Personnel Injury / Environmental Pollution	2	3	6	All personnel must be aware of their surrounds and weather conditions. Use proper Manual Handling techniques, i.e., Always use proper body positioning, lift with legs, and obtain second personnel when loads are over 40lbs. Read all SDS on chemicals used, use PPE that is specified in SDS and be aware of where all spill kits are located.	2	2	4
3	Use of hand tools.	Pinch points, cuts, stabs, trip and slip hazard	Personnel Injury / Environmental Pollution	2	2	4	Use proper PPE for the task. Use hand tools properly for their use. Keep tools clean and secured when not in use. Do not leave tools laying around in walkways or staircases	1	1	1
4	Check all equipment being used for task	Damage to equipment, Environmental spills, burst air hose, personnel injury.	Personnel Injury / Environmental Pollution	2	2	4	Check air hose for damage or wear, if found take out of service. Check pump for wear or damage and take out of service and inform supervisor.	1	1	1
5	Set up oil transfer pump	Environmental spills, slips trips and falls, damage to equipment	Personnel Injury / Environmental Pollution	2	2	4	Ensure that all hoses are secured to prevent spills or environmental discharge. Have oil absorbent diapers and spill kit on hand. MSDS on hand. <i>When using pump flush all lines when different oil is being transferred.</i>	1	1	1
6	Begin transferring oil	Inhalation, ingestion, skin irritation with personnel. Slip hazard, chemical reactions	Personnel Injury / Environmental Pollution	2	2	4	NEVER leave location as oil is being transferred. Have oil absorbent diapers and spill kit on hand during transfer. MSDS on hand. Use proper PPE during transfer of oil.	1	1	1

7	Clean up all areas of all tools and equipment. Clean and stow all tools in proper location	Slip trips and falls. Dropped objects and hydraulic discharge.	Personnel Injury / Environmental Pollution	2	2	4	Clean and put away all tools and chemicals in their proper locations. Secure all ladders and ropes if used.	1	1	1
8	Close all oil totes.	Environmental spills, slips, trips, and falls. Oil Contamination.	Personnel Injury / Environmental Pollution	2	2	4	Ensure that oil totes have been closed to prevent contamination of oil from rain or debris.	1	1	1

TRA Approval	Name	Position	Signature	Date
By signing, the Approver confirms that the TRA has been reviewed and considers the task acceptable to proceed with residual risk meeting the acceptance criteria of DO Risk Matrix.				

*Reference DO-HSE-FRM-140 for DeepOcean Risk Assessment Matrix (RAM) and Guidewords